



**PLAN VIEW**

- NOTES :**
1. BACKFILL, BEDDING AND BUOYANCY DESIGN BY ENGINEER OF RECORD.
  2. FILTERRA® UNIT FITTED WITH SWIFTLIFT OR HAIRPIN LIFTING POINTS. SPREADER BARS REQUIRED TO AVOID DAMAGE TO CONCRETE EDGES DURING OFF-LOADING.
  3. TO PROTECT MEDIA FROM CONSTRUCTION RELATED EROSION RUNOFF, FILTERRA® UNIT IS DELIVERED WITH BOXING OVER MEDIA. BOXING TO BE REMOVED **ONLY** BY STORMWATER360® DURING COMMISSIONING.
  4. MULCH, PLANTING AND ROCK SCOUR TO BE INSTALLED DURING COMMISSIONING BY STORMWATER360®. COMMISSIONING TO OCCUR ONLY WHEN PAVEMENT IS INSTALLED, AND SITE IS CLEAN.
  5. PLANT SELECTION BY OTHERS BASED ON STORMWATER360® PLANT GUIDE.
  6. CALL **0800STORMWATER** FOR COMMISSIONING.
  7. OVERFLOW BYPASS CATCH PIT TO BE INSTALLED DOWNSTREAM OF FILTERRA® UNIT.
  8. RECOMMENDED THAT FLEXIBLE COUPLINGS USED ON OUTLET TO ALLOW FOR POTENTIAL SETTLEMENT.
  9. CONCRETE STRUCTURE DESIGNED TO HN-72.




**SPLIT KERB DETAIL**

RECOMMENDATION ONLY (BY OTHERS)



**SECTION A-A**



**SECTION B-B**

**ESTIMATED WEIGHT :**  
**CONCRETE VAULT + MEDIA**  
**+ DRAINAGE LAYER**  
**MASS = 9700 Kg**



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 6,277,274; 6,568,321; 7,625,485; 7,425,261; 7,533,412; RELATED FOREIGN PATENTS.



0800 STORMWATER

sales@stormwater360.co.nz

www.stormwater360.co.nz

**CONDITION OF USE**

© STORMWATER360 2019  
 Any unauthorised reproduction of this drawing in part or in full is prohibited

**FILTERRA®**  
**STORMWATER BIOFILTRATION**  
**OPEN TOP / SHALLOW DEPTH 3600 x 1200 (INSIDE)**  
**GENERAL ARRANGEMENT**

SCALE : NTS    DRG No : FT-OT-SH-3612-20    REV : 1    DATE : 04.02.19

JOB NO :		REV	REVISION DETAIL	DATE
PROJECT :		0	FIRST ISSUE	04.02.19
DRN :	R.P.	04.02.19		
CKD :	G.S.	G.Y.	04.02.19	
			1	DWG No. CHANGE
				27.03.19