



PLAN VIEW

- NOTES :**
1. BACKFILL, BEDDING AND BUOYANCY DESIGN BY ENGINEER OF RECORD.
 2. FILTERRA® UNIT FITTED WITH SWIFTLIFT OR HAIRPIN LIFTING POINTS. SPREADER BARS REQUIRED TO AVOID DAMAGE TO CONCRETE EDGES DURING OFF-LOADING.
 3. TO PROTECT MEDIA FROM CONSTRUCTION RELATED EROSION RUNOFF, FILTERRA® UNIT IS DELIVERED WITH BOXING OVER MEDIA. BOXING TO BE REMOVED **ONLY** BY STORMWATER360® DURING COMMISSIONING.
 4. MULCH, PLANTING AND ROCK SCOUR TO BE INSTALLED DURING COMMISSIONING BY STORMWATER360®. COMMISSIONING TO OCCUR ONLY WHEN PAVEMENT IS INSTALLED, AND SITE IS CLEAN.
 5. PLANT SELECTION BY OTHERS BASED ON STORMWATER360® PLANT GUIDE.
 6. CALL **0800STORMWATER** FOR COMMISSIONING.
 7. OVERFLOW BYPASS CATCH PIT TO BE INSTALLED DOWNSTREAM OF FILTERRA® UNIT.
 8. RECOMMENDED THAT FLEXIBLE COUPLINGS USED ON OUTLET TO ALLOW FOR POTENTIAL SETTLEMENT.
 9. CONCRETE STRUCTURE DESIGNED TO HN-72.




SPLIT KERB DETAIL

RECOMMENDATION ONLY
(BY OTHERS)



SECTION A-A



SECTION B-B

ESTIMATED WEIGHT :
CONCRETE VAULT + MEDIA
+ DRAINAGE LAYER
MASS = 8000 Kg



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 6,277,274; 6,569,321; 7,625,485; 7,425,261; 7,833,412. RELATED FOREIGN PATENTS.



0800 STORMWATER
 sales@stormwater360.co.nz
 www.stormwater360.co.nz

CONDITION OF USE
 © STORMWATER360 2019
 Any unauthorised reproduction of this drawing in part or in full is prohibited

FILTERRA®
STORMWATER BIOFILTRATION
OPEN TOP / STANDARD DEPTH 1800 x 1800 (INSIDE)
GENERAL ARRANGEMENT

SCALE : NTS DRG No : FT-OT-ST-1818-20 REV : 1 DATE : 01.02.19

JOB NO :	REV	REVISION DETAIL	DATE
PROJECT :	0	FIRST ISSUE	01.02.19
DRN :	1	DWG No. CHANGE	27.03.19
CKD :	R.P.	G.Y.	01.02.19
	G.S.	G.Y.	01.02.19