


TO BE COMPLETED BY SW360									
SW360 PRODUCT CODE :									
MEDIA TYPE (CIRCLE ONE):	PERLITE	ZPG	OTHER:						
CARTRIDGE QTY (STATE):	PRE-INSTALLATION (Y/N):								
SP FLOW RATE (CIRCLE ONE):	FULL (Ø 25.0 ID) RED	3 QTR (Ø 21.8 ID) GREY	HALF (Ø 17.9 ID) ORANGE	OTHER:					
ACCESS COVER (CIRCLE ONE):	ALLOY CHE	QUER PLATE	OTHER:						
COMPLETED BY :	SIGNED :		DATE:						

## **SW360 PRODUCTION DATA**

## **OUTLET HOLE DETAILS:**

(CIRCLE REQUIREMENT)



DWG ISSUE No.:

**REQUIRED DATE:** 

## NOTES

- . MANHOLE UNIT FITTED WITH SWIFTLIFT ANCHOR POINTS (QTY 2). DO NOT EXCEED 60 DEGREE LIFT ANGLE.
- 2. UNIT SUPPLIED WITH OUTLET CORE DRILLED. INLET/S CORE DRILLED ON SITE BY OTHERS WITHIN RANGE SHOWN ON DRAWING.
- SEALING / GROUTING OF MANHOLE COMPONENTS AND PIPES BY CONTRACTOR. ENSURING LOCAL CODES AND REGULATIONS ARE COMPLIED WITH.
- ANY RISERS REQUIRED TO INCREASE THE DEPTH TO INVERT (DTI) FROM THAT AS DRAWN TO BE SUPPLIED BY THE CONTRACTOR.
- FROM THAT AS DRAWN TO BE SUPPLIED BY THE CONTRACTOR.

  FOR A DTI EXCEEDING 5m PLEASE CONTACT **0800STORMWATER**
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION RELATED EROSION RUNOFF.
- BACKFILL, BEDDING AND BUOYANCY DESIGN BY ENGINEER OF RECORD
- . QTY OF CARTRIDGES BY ENGINEER OF RECORD.
- CONCRETE MANHOLE RISERS ARE DESIGNED AND MANUFACTURED IN ACCORDANCE WITH AS/NZS 4058 : 2007
- . CONCRETE MANHOLE BASES ARE DESIGNED AND MANUFACTURED IN ACCORDANCE WITH NZS 3101 : 2006 & NZS 3109 : 1997
- 11. ALUMINIUM LID / NON-TRAFFICABLE
- 12. FOR REQUIREMENTS OUTSIDE OF DRAWING SPECIFICATIONS PLEASE CONTACT **0800STORMWATER**.

## **APPROX WEIGHTS**

MANHOLE SECTION INCLUDING CARTRIDGES: **2450 Kg** (AS DELIVERED, BASED ON QTY 4 ZPG CARTS)



oson Stormwater Condition of USE

sales@stormwater 360.co.nz

sales@stormwater 360.co.nz

condition of USE

© Stormwater 360 2019
Any unauthorised reproduction of this drawing in part or in full is prohibited

STORMFILTER®
CARTRIDGE FILTRATION SYSTEM
46cm CART / DN1500 x 1200 MH : NON - TRAFFICABLE
GENERAL ARRANGEMENT

SCALE : NTS DRG No : SF-MH-46-1500-NT-20 REV : 2 DATE : 01.03.19

JOB NO:				REV	REVISION DETAIL	DATE
PROJECT:				0	APPROVED	01.03.1
				1	MARK-UPS	09.04.1
DRN:	R.P.		01.03.19	2	CORRECTION	17.03.2
CKD:	G.S.	G.Y.	01.03.19			