



PLAN VIEW
(LID OMITTED)



SECTION A-A



SECTION B-B

TO BE COMPLETED BY CUSTOMER / CONTRACTOR

| | | | |
|---|-----------------|----------------|---------------|
| COMPANY : | P.O. NUMBER : | | |
| SITE ADDRESS : | | | |
| SITE CONTACT & PHONE : | | | |
| PREFERRED DELIVERY DATE (TBC SW360) : | | | |
| STORMFILTER REFERENCE (IF APPLICABLE) : | | | |
| INLET PIPE Ø : | PIPE MATERIAL : | CORE DRILL Ø : | INLET (IL) : |
| OUTLET PIPE Ø : | PIPE MATERIAL : | CORE DRILL Ø : | OUTLET (IL) : |
| LID LEVEL (RL) : | DTI : | | |
| COMPLETED BY : | SIGNED : | DATE : | |

TO BE COMPLETED BY SW360

| | | | | | |
|------------------------------|--------------------------|-------------------|------------------|---------|---------|
| SW360 PRODUCT CODE : | PERLITE | | | ZPG | OTHER : |
| MEDIA TYPE (CIRCLE ONE) : | | | | | |
| CARTRIDGE QTY (STATE) : | PRE-INSTALLATION (Y/N) : | | | | |
| SP FLOW RATE (CIRCLE ONE) : | FULL (Ø 27.6 ID) | 3 QTR (Ø 24.0 ID) | HALF (Ø 19.7 ID) | OTHER : | |
| ACCESS COVERS (CIRCLE ONE) : | BLACKMUSTARD | WHITE/OPAL | GREEN | | |
| COMPLETED BY : | AS DRAWN - YES or NO | OTHER : | DATE : | | |
| SIGNED : | | | DATE : | | |

APPROX WEIGHTS
 VAULT WEIGHT: 21200 Kg (EMPTY)
 VAULT WEIGHT: 22550 Kg (WITH 27 x ZPG CARTS FITTED)
 LID WEIGHT: 7300 Kg

NOTES

- SW360 TO CONFIRM WEIGHTS AND LIFTING DETAILS PRIOR TO DELIVERY.
- UNIT SUPPLIED WITH INLET & OUTLET HOLES PRE-CORED.
- INLET AND OUTLET PIPES BY OTHERS.
- SEALING / GROUTING OF CONCRETE LID AND PIPES BY CONTRACTOR, ENSURING LOCAL CODES AND REGULATIONS ARE COMPLIED WITH.
- RISERS REQUIRED FROM VAULT LID TO ACCESS COVERS (FINISHED SURFACE LEVEL) SUPPLIED BY THE CONTRACTOR. CONTACT **0800STORMWATER** FOR RECOMMENDATIONS.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION RELATED EROSION RUNOFF.
- BACKFILL, BEDDING AND BUOYANCY DESIGN BY ENGINEER OF RECORD.
- QTY OF CARTRIDGES BY ENGINEER OF RECORD.
- CONCRETE VAULT AND LID DESIGNED AND MANUFACTURED TO HN-HO-72
- DESIGN CHECK REQUIRED WHEN COVER ABOVE LID EXCEEDS 1.0M
- OTHER CONFIGURATIONS ARE POSSIBLE. FOR REQUIREMENTS OUTSIDE OF DRAWING SPECIFICATIONS PLEASE CONTACT **0800STORMWATER**.



0800 STORMWATER
 sales@stormwater360.co.nz
 www.stormwater360.co.nz

CONDITION OF USE
 © STORMWATER360 2020
 Any unauthorised reproduction of this drawing in part or in full is prohibited

STORMFILTER@ PEAK DIVERSION
 OFF-LINE CARTRIDGE FILTRATION SYSTEM
 27 x 69cm CART PD VAULT (LEFT INLET)
 GENERAL ARRANGEMENT

SCALE : N.T.S. DRG No : SF-VPD-69-4230-L-20 REV : 1 DATE : 01/04/20

| | | | |
|-----------|-----|-----------------|----------|
| JOB NO : | REV | REVISION DETAIL | DATE |
| PROJECT : | 1 | WEIGHTS ADDED | 01/04/20 |
| DRN : | 0 | APPROVED | 18/03/20 |
| G.S : | | | |
| K.J : | | | |